

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
06-01-1972  
JUN 1 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-153-20137-00-00

Operator's Full Name Halliburton Oil Producing Company,  
Complete Address 117 Cameron Building, Oklahoma City, Oklahoma. 73106  
Lease Name Solko Well No. 1  
Location CNE-NE Sec. 19 Twp. 1 Rge. (E) (W) 31  
County Rawlins Total Depth 4085'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center Building, Wichita, Kansas. License No.       
Operation Completed: Hour 5:30 AM Day 30 Month 5 Year 1972

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1600'.

Circulated hole with heavy mud. Pulled DP to 1825' and displaced 110 Cu. Ft. cement  
thru DP from 1825' to 1500'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Pichals  
Well Plugging Supervisor

INVOICED

DATE 6-1-72  
INV. NO. 5788-W