

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30003-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11-18-1963
NOV 18 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Green Well No. 1

Location CSW-NE Sec. 24 Twp. 1 Rge. (E) (W) 31

County Rawlins Total Depth 4445

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:30PM Day 15 Month 11 Year 1963

The Above well was plugged as follows:

127'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 120', set plug with 1/4 sack hulls & displaced

20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls &

10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/19/63

INV. NO. 8125-W