

KANSAS

90

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1967
05-31-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-153-20010-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name Sattler Well No. 1

Location CNW-NE Sec. 18 Twp. 1 Rge. (E) (W) 31

County Rawlins Total Depth 4107

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No.

Operation Completed: Hour 3:30AM Day 27 Month 5 Year 1967

The Above well was plugged as follows:

288'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Circulated hole with heavy mud, set plug @ 660' and displaced 15 Sx.
cement thru DP. Heavy mud to 300', set plug with 1/4 sack hulls and dis-
placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Nichols
Well Plugging Supervisor

DATE 5/31/67

INV. NO. 5306-W