

6 031126

6-23

15-153-20230-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1975
75W SW SW, SEC. 17, T 1 S, R 32

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Operator: Donald C. Slawson
Name & Address: 104 S. Broadway
Wichita, Ks. 67202

660 feet from S section line

4695 feet from E section line

Lease Name Wicke Well # C 4

County Rawlins 134.88

Well Total Depth 4150 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address Ness City, Ks.

Company to plug at: Hour: AM Day: 23 Month: June Year: 19 88

Plugging proposal received from Joe

(company name) Cheyenne (phone)

were: 8 5/8" set at 369' w/250 sks cwc. 4 1/2" set at 3785' w/125 sks

Perfs 3932' - 4038'. Order sand and Common Cement. Pull pipe.

Order 250 sks Cement Blend 500# Hulls. Allied Cement Co. Cheyenne Water

Trucks.

RECEIVED
STATE CORPORATION COMMISSION
09-16-1988
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent Part None

Operations Completed: Hour 10:15AM Day: 23 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3794' w/4 sks cement on sand w/bailer.

Free point, shot and reovered 1800' of 4 1/2" casing.

Squeezed 8 5/8" w/250 sks cement w/500# Hulls mixed in to max Psi 400#. Close in 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(I, the undersigned, do hereby certify this plugging.)

DATE 9-20-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22330

Carl Goodrow