

6 031,172

10-4

408

R

API NUMBER 15-15320083-00-01
S E NE, SEC. 17, T 1 S, R 32 W/E

3300 feet from S section line
660 feet from E section line

Lease Name Wicke Well # 2-~~3~~
County Rawlins 134.58

Well Total Depth 4150' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet ?

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5100

Operator: Kern Company

Name & Address 3005 Big Springs St.

Midland, Tx. 79701

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 4 Month: Oct Year: 19 88

Plugging proposal received from E. E. Goodrich

(company name) Kern Co. (phone) _____

were: Through tubing on bottom 50 sks Common Cement. Mud up to 2290' w/60/40

Poz 8% Gel to surface. Test backside w/50 sks 60/40 Poz 8% Gel. Order 195 sks 60/40 Poz 8% Gel 50- sks common cement 15 sks gel. Halliburton Cmt. Co. Webb Water Truck

Perforated at 2125' - 27' 10 shots.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Don Butcher
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 12:00PM Day: 4 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pump down tubing 50 sks common cement on bottom. Laid down tubing (250 +). Tied onto backside pump 50 sks cement blend to 200# Psi. Closed in at 100# psi. Tie back onto tubing. Pump cement blend to circulate to surface. Total of 145 sks. Plug complete.

Remarks: MIT failed (attached)
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to observe this plugging.

DATE 11-9-88

INV. NO. 22960

Signed Carl Goodrich
Carl Goodrich (TECHNICIAN)