

4-032318

E-25,583

9-18

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,113 00 01

C SE SW /4 SEC. 17, 01, 32 W
660 feet from S section line
3300 feet from E section line

Operator license# 3602

Lease: H.J. Wicke Well # 1

Operator: Philpott Oil & Gas Co., Inc.

County: Rawlins 135.53

Address: P.O. Box 450
Atwood, Kansas 67730

Well total depth 4170 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 354 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 18 Month: September Year: 1998

Plugging proposal received from: Philpott

Company: Philpott Oil & Gas Company, Inc. Phone: -

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:15 A.M., Day: 18 Month: September, Year: 1998

Actual plugging report: 8 5/8" set at 354' w/250 sxs cwc. 5 1/2" set at 4169' w/300 sxs. Squeezed at 3700' - 4000'; 2700' - 2200' with 500 sxs. Squeezed 5 1/2" with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 100#. Held. Squeezed 8 5/8" with 25 sxs cement blend to Max. P.S.I. 300#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

09-30-1998

INVOICED

DATE 10-2-98

INV. NO. 51402