

6-24 15-153-20097-00-01

6 031128

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-1970
C NW SW, SEC. 18-17, T 1 S, R 32 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Wicke Well # C-1 SWD

Operator: Donald C. Slawson

County Rawlins 134.55

Name & Address 104 S. Broadway

Well Total Depth 4140 feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated 98323-C E-16, 985

Plugging Contractor Cheyenne Well Service License Number 6454

Address Ness City, Ks.

Company to plug at: Hour: AM Day: 24 Month: June Year: 19 88

Plugging proposal received from Joe

(company name) Cheyenne (phone) _____

were: 8 5/8" set at 358' w/250 sks cwc. 4 1/2" set at 4139' w/150 sks.

Perf 3901' - 4082'. Order sand and Common cement. Pull pipe

Order 250 sks Cement Blend 500# Hulls. Allied Cement Co.

Cheyenne Water Trucks.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:00AM Day: 24 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3850' w/4 sks cement on sand w/bailer.

Shots at 2100' and 1800'. Recovered 1800' of 4 1/2" casing. Squeezed 8 5/8"

w/250 sks cement w/500# Hulls mixed into max Psi 600#. Close in

300#. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I will not serve this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

D

DATE 9-20-88

INV. NO. 22332