

8-14

4-032252

15-153-00031-00-01

E-17,400

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1959

SE SE SE /4 SEC. 17, 01, 32 W
330 feet from S section line
330 feet from E section line

Operator license# 3602

Lease: Wilhelm Unit Well # 2

Operator: Philpott Oil & Gas

County: Rawlins 137.35

Address: P.O. Box 450
Atwood, Kansas 67730

Well total depth 4226 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 448 feet
W/300 sxs.

Aband. oil well___, Gas well___, Input well X, SWD___, D & A___

Plugging contractor: Allied Cement Company License# -

Address: Russell Kansas 67665

Company to plug at: Hour: P.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Roger Philpott

Company: Philpott Oil & Gas Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 14 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 448' w/300 sxs cwc. 5 1/2" set at 4217' with 250 sxs. Prod. Perf. At 3958' - 4093'. Shot at 2200' - 1600'. No stretch in pipe cement near surface. CIBP at 3900' w/4 sxs cement on top. Squeezed 5 1/2" w/100 sxs cement blend with 500# hulls. Blew out casing hole full. Fill backside with 1/2 BBL. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 9-16-97

INVOICE NO. 49019

8-14