

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20131-00-00

RECEIVED
STATE CORPORATION COMMISSION
12-15-1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Wicke Well No. 1

Location CSE-NW Sec. 17 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 7:00 PM Day 12 Month 12 Year 1971

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1850'.

Circulated hole with heavy mud. Pulled DP to 2075' and displaced 110 Cu. Ft. cement
thru DP from 2075' to 1750'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/15/71
INV. NO. 4820-w