

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20341-00-00

LEASE NAME Wells Unit

WELL NUMBER 29-3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

766 Ft. from ^N Section Line
1874 Ft. from ^W Section Line

SEC. 29 TWP. 19 RGE. 20W (E) or (W)

COUNTY Rush

EASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. N. Bldg. 300 Wichita, Ks. 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed 9-16-1970

Character of Well Oil

Plugging Commenced 4-8-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-12-04

The plugging proposal was approved on 3-25-04 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4450' 4445'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				9-5/8"	357'	None
				4-1/2"	4447'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 4300' and 4 sacks cement. Perforated 4-1/2" casing @600ft. Tied onto 4-1/2" casing and pumped 150 sacks cement Max. press. 1000#. Tied onto backside and pumped 50 sacks cement. 60/40 pos. 6% gel. Shut in Press. 500#
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of April, 20 04

Notary Public

My Commission Expires: _____



RECEIVED

APR 22 2004

KCC WICHITA