

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-22616-00-00

LEASE NAME Eisenberg

WELL NUMBER 1

330 Ft. from ^N Section Line

2310 Ft. from ^W Section Line

SEC. 27 TWP. 18 RGE. 11W(E)or(W)

COUNTY Barton

Date Well Completed 3-16-1982

Plugging Commenced 4-12-04

Plugging Completed 4-13-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Vess Oil Corporation
ADDRESS 8100 E. 22nd. St. N. Bldg. 300 Wichita, Ks. 67226

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-2-04 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>				<u>8-5/8"</u>	<u>222'</u>	<u>None</u>
<u>Sand</u>				<u>4-1/2"</u>	<u>3345'</u>	<u>2017'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 2950' and 4 sacks cement. Cut pipe loose @2017'. pulled up to 1350'. pumped 65 sacks cement and 200# hulls. pulled up to 600'. pumped 40 sacks cement and 100# hulls. pulled up to 150' and circulated 40 sacks cement to surface. Topped off with 15 sacks. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed thereon and the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

[Signature]
Notary Public

My Commission Expires:



RECEIVED

APR 22 2004

KCC WICHITA