

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20522-00-00<sup>23</sup>

LEASE NAME Hamm

WELL NUMBER 3

1980 Ft. from S Section Line

3300  
4300 Ft. from E Section Line

SEC. 14 TWP. 33 RGE. 30 (W)

COUNTY Meade

Date Well Completed 1-30-82

Plugging Commenced 3-12-04

Plugging Completed 3-16-04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sunfire Energy

ADDRESS P.O. Box 1761 Liberal KS. 67905

PHONE(S) (620) 624-7031 OPERATORS LICENSE NO. 32126

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-18-04 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Marmaton Depth to Top 5207 Bottom 5210 T.O. 5450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				20	43	0
				8 5/8	1623	4
				4 1/2	5450	2503

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each s  
Mixed 200 lb. hulls & 20 sx cmt. to plug perfs from 5207 to 5007. Shot & pull 4 1/2 to 1650 Circ. hole w/mud & mixed 50 sx cmt. 1650 to 1500 30 sx 550 to 450 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gerald M Roberts DRA Sunfire Energy

STATE OF Kansas COUNTY OF Seward , ss. 514-52-3656 32126 <sup>OP #</sup>

Gerald M Roberts Sunfire Energy (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well, as filed with the same are true and correct)

NOTARY PUBLIC STATE OF KANSAS  
TAWANDA L. LEWIS  
My Appt. Expires 8-20-07

(Signature) Gerald M Roberts

(Address) P.O. Box 1761 Liberal KS 67905

RECEIVED

APR 22 2004

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 20th day of April 2004

My Commission Expires: Aug 20 2007 Notary Public