

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02251-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 19-9S-20W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: COPELAND Well #: 8  
County: ROOKS Total Vertical Depth: 3788 feet

Operator License No.: 9449  
Op Name: GREAT EASTERN ENERGY & DEV. CO  
Address: 550 W. TEXAS STE 660  
MIDLAND, TX 79702

PROD Size: 7 feet: 3788  
SURF Size: 10.75 feet: 215

*A 123"*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2002 12:00 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: MIKE DAVIGNON Company: GREAT EASTERN ENERGY & DEV. Phone: (915) 682-1178

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 700# hulls - 25 sxs gel.  
Perfs 2300' - 1825' - 1100' - 200'.

Plugging Proposal Received By: ~~HERB DEINES~~  
Date/Time Plugging Completed: 04/04/2002 5:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

Ran tubing to 3780' - pumped 25 sxs gel plus 50 sxs cement with 300# hulls.  
Pulled to 2300' - pumped 100 sxs cement with 200# hulls.  
Pulled to 1100' - circulated to surface with 125 sxs cement with 200# hulls.  
Pulled tubing. Pumped 20 sxs down casing.  
Pumped 20 sxs cement down 10 3/4" surface pipe.

RECEIVED  
APR 22 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Dennis J. Hamel*  
(TECHNICIAN)

INVOICED

DATE 4-23-04

INV. NO. 2004061453

Form CP-2/3

APR 14 2004

INDEXED

SINCLAIR OIL & GAS #8 COPELAND 19-9-20W 22  
 NE SW NW

Contr. \_\_\_\_\_ ROOKS County

E 2246RB Comm. \_\_\_\_\_ Comp. 6-15-51 IP 2822 BOPD  
 DRAW DOWN

Tops	Depth	Datum
HEEB	3458	-1212
LANS	3499	-1253
CONG	3756	-1510
SIMP	3770	-1524
ARB	3781	-1535
T.D.	3788	-1542

Casing  
 10" 215 DD 3788  
 5" 3782 2800' OIH  
 ACID 1000  
 SWB 8 BOPH

GRA-ROOK POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS