

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21108-00-00  
Spot: SENENWSW Sec/Twnshp/Rge: 21-34S-2E  
2185 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: WALIN A Well #: 2-21  
County: SUMNER Total Vertical Depth: 3240 feet

Operator License No.: 32753  
Op Name: PAUL C. CARAGEANNIS DBA SEED GR  
Address: PO BOX 771189  
WICHITA, KS 67277

PROD Size: 4.5 feet: 3234 150 sacks

#105<sup>30</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2004 12:00 AM  
Plug Co. License No.: 32753 Plug Co. Name: PAUL C. CARAGEANNIS DBA SEED GROUP  
Proposal Rcvd. from: PAUL C. CARAGEANNIS Company: PAUL C. CARAGEANNIS DBA SEE Phone: (316) 838-5870

Proposed Plugging Method: Perfs 3061'-3069'; 3164'-3170'; 3170'-3176'; 2861'-2864'.

Plugging Proposal Received By: STEVE VANGIESON  
Date/Time Plugging Completed: 04/08/2004 4:00 PM

Witness Type: PARTIAL  
KCC Agent: DAVE WERTZ

RECEIVED  
KCC DISTRICT #2

APR 20 2004

WICHITA, KS

Actual Plugging Report:

Perfs:

Set CIBP at 2810' and capped with 4 sacks of cement. Shot off 4-1/2" at 1376' and pulled from wellbore. Ran 1-1/4" polly coil to 275'. Circulated cement to surface with 120 sacks of 60/40 with 4% gel.

Cementing done by Gressel Cement.

4/9/2004 -- Steve Van Gieson checked cement down 30'.

4/14/2004 -- Well was topped off.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 23 2004

CONSERVATION DIVISION  
WICHITA, KS

Remarks: PLUGGED THROUGH POLLY COIL.

Plugged through:

District: 02

Signed

David Wertz

(TECHNICIAN)

INVOICED

DATE

4-23-04

INV. NO.

2004061449