

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. - 82-3-117

API NUMBER 15-195-20513-00-00

LEASE NAME Baughner

WELL NUMBER B-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 22 TWP. 12 RGE. 21W (E) or (W)

COUNTY Trego

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS P.O. Box 780428 Wichita, Kansas 67278-0428

PHONE (316) 684-9777 OPERATORS LICENSE NO. 5141

Date Well Completed 1-31-1979

Character of Well Oil

Plugging Commenced 4-8-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-8-04

The plugging proposal was approved on 2-27-04 (date)

by Roger Moses (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>138</u>	<u>8-5/8"</u>	<u>138'</u>	<u>None</u>
<u>prod</u>			<u>3966</u>	<u>4-1/2"</u>	<u>3966'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 3900' and 4 sacks cement. Perforated 4-1/2" casing @2200 ft. 1325 ft. & 200 ft. Ran 2" tubing to 2200 ft., pumped 50 sacks cement, 300# hulls and 100 sacks cement and circulated. Pulled 2" tubing out, tied onto backside, pumped 75 sacks cement and shut-in. Tied onto 4-1/2" casing and pumped 25 sacks cement. 60/40 pos. 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Zenith Drilling Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED KANSAS CORPORATION COMMISSION
RECEIVED KANSAS CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

APR 23 2004 APR 23 2004

[Signature]
Notary Public

CONSERVATION DIVISION WICHITA, KS My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05