

3-27

198 R

4-071091

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,799-00-00

NW SW SW /4 SEC. 30, 01 S, 31 W
990 feet from S section line
330 feet from E section line

Operator license# 5131

Lease Wahrman well # 1

Operator: Thunderbird Drilling, Inc.

County Rawlins

Address: P.O. Box 780407
Wichita, Kansas 67278
Burke B. Krueger

Well total depth 4120 feet ^{133.90}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 296 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie Drilling License# 30684

Address: Wichita, Kansas 67278

Company to plug at: Hour: A.M. Day: 27 Month: March Year: 94

Plugging proposal received from: Tony Martin

Company: Abercrombie Drilling Phone: 316-685-1441

Were: 8 5/8" - 296' S.P. cwc. w/185 sxs. 60/40 pozmix - 2% gel -
3% C.C. By Allied Cementing. Elv. 2883' - Anhy. 2683' - No circulation
problems - No ar buckle - Mud condition 50 vis. - 9.2 wt. - W.L. 8.8 -
Chlorides 1500 ppm at 3900'. Proposal 190 sxs. 60/40 pozmix - 6% gel and
1 sx. F.C. Circulate hole - spot and displace all cement through drill
stem - heavy mud between all plugs. 25 sxs. at 2730' - 100 sxs. with one
sx. F.C. at 1980' - 40 sxs. at 345' - 10 sxs. at 40' - 15 sxs in rathole
(circulate)

Plugging Proposal Received by: Marion J. Schmdit
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:00P.M., Day: 27, Month: March, Year: 94

Actual plugging report: Abercrombie Drilling ordered 190 sxs. 60/40
pozmix - 6% gel and one sack flocele. Circulated hole - spot and
displaced all cement through drill pipe with heavy mud between all plugs.
1st. plug at 2730' w/25 sxs. cement.
2nd. plug at 1980' w/100 sxs. cement with 1 sx. flocele.
3rd. plug at 345' w/40 sxs. cement.
4th. plug at 40' w/10 sxs. cement.
15 sxs. in rathole (circulated)

RECEIVED
STATE CORPORATION COMMISSION
4-05-1994
APR 05 1994

Remarks: By Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X NO
Plugged through TUBING X, CASING . Elevation: 2883 GL Wichita, Kansas

I did not [X] observe the plugging.

Marion J. Schmdit
(agent)

INVOICED

DATE 4-18-94

INV. NO. 40301

3-27