



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas
11-29-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Massey & Moore,

Complete Address: Box #592, Cushing, Oklahoma.

Lease Name: Kastens Well No. 1

Location: CNW-SW Sec. 14 Twp. 1 Rge. (E)(W) 32

County: Rawlins Total Depth 4265' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakotasection @ 1800'.

Circulate hole with heavy mud. Pull DP to 2025' and displace 100 Sx.
cement thru DP. Pull DP to 370' and displace 25 Sx. cement thru DP.
Pull DP, set btidge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent