

State of Kansas



15-153-20189-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1974  
12-9-1974  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Farmer of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Farmer guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Grill Well No. 1

Location: CSE-SE Sec. 1 Twp. 1 Rge. (E)(W) 32

County: Rawlins Total Depth 4235' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Farmer was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 165 Sx.

Circulate hole with heavy mud. Pull DP to 2100' and displace 70 Sx. cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Diehls  
Conservation Division Agent