

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-153-20083-00-01  
 API NUMBER 15-153-200-83

LEASE NAME E. W. Wicke

WELL NUMBER 2

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 17 TWP. 1-SRGE. 32 (X) or (W)

COUNTY Rawlins

Date Well Completed 11-16-70

Plugging Commenced 10-4-88

Plugging Completed 10-5-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Kern Co.

ADDRESS 3005 N. Big Spring St., Midland, TX 79705

PHONE#(915) 683-4832 OPERATORS LICENSE NO. 5100

Character of Well SWD EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Oct. 3, 1988 On Phone by Mr. Don Butcher (date)

by Mr. Carl Goodrow witnessed plugging (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing K.C. Depth to Top 3903 Bottom 4150 T.D. 4150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing K.C.	Oil and Water	3903'	4150'			
		Surface	4150'	5 1/2"	4150'	3'
		Surface	301'	8 5/8"	301'	3'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 5 1/2" csg from 2125' to 27' w 10 shots. Ran tubing to PBT 4134' and spotted 50 sx cement on bottom. Pulled tubing to top of cement 3709' and circulated Halliburton gel to 2125'. Pumped 145 sx 60-40 poz w/8% gel down braden head and filled the 5 1/2" csg to the surface w cement down tubing. Pulled tbg, filled hole w cement and abandoned well.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton cementing Co. License No. 5287

Address P. O. Box 428, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kern Co.

STATE OF Texas COUNTY OF Midland

William G. Kern (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William Kern

(Address) 3005 N. Big Spring St. Midland, TX 79705



ROBERTA L. BARTLEY  
 NOTARY PUBLIC STATE OF TEXAS  
 COMMISSION EXPIRES 6-20-89

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 88

Roberta L. Bartley  
 Notary Public

My Commission Expires: June 20, 1988

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 10 1988  
 CONSERVATION DIVISION  
 WICHITA, KANSAS