

Q

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20038-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1969
CONSERVATION DIVISION
Wichita, Kansas
1-8-69

Operator's Full Name Murfin Drilling Company and J. S. Kantor,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Horinek Well No. 1

Location App. -CNE-NE Sec. 4 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 2700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Lost circulation @ 2595', dry drilled to 2700' was unable to regain circulation. Shot off DP @ 1981' and abandoned hole.

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kans. License No.

Operation Completed: Hour 6:30 PM Day 4 Month 1 Year 1969

The Above well was plugged as follows:

259'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1675'. Well had sanded off on bottom, was able to circulate hole from 1900'.

Circulated hole with heavy mud and displaced 100 Sx. cement thru DP from 1900' to 1575'. Pulled DP to 270' and displaced 25 Sx. cement thru DP from 270' to 195'.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-8-69

INV. NO. 9162-W