

KANSAS

V STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20156-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1973
CONSERVATION DIVISION
Wichita, Kansas
5-22-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Vap Well No. B-1

Location Appr:-SE-SE-SE Sec. 4 Twp. 1 Rge. (E) (W) 23

County Rawlins Total Depth 4110'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 West Wichita, Russell, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 19 Month 5 Year 1973

The above well was plugged as follows:

227'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 110 Cu. Ft. cement
thru DP from 2025' to 1700'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 5/22/73
WELL NO. 1387-W