

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
15-153-20001-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1967
2-6-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Peterson Well No. 1

Location CSE-NW Sec. 6 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4685

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 2:30PM Day 29 Month 1 Year 1967

The Above well was plugged as follows:

200'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/9/69
4117-4
INV. NO. _____

Signed: N. L. Nichols
Well Plugging Supervisor