

KANSAS

*AL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20026-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-17-70

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Peterson Well No. 1

Location SE-SE-SW Sec. 6 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4120

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor David Liton Cable Tools,

Address Box #1137, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 12:30 PM Day 13 Month 11 Year 1970

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 165 Sx.

4117'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3002'. Bridging plug set @ 2200' and 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and followed with 100 Sx. cement from 2025' to 1700' then 32 sacks gel from 1700' to 250' and followed with 25 Sx. cement from 250' to 175' then 3 sacks gel from 175' to 35' and finally 10 Sx. cement from 35' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-325#. (Mudding and cementing operations by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*  
Well Plugging Supervisor

DATE 11/17/70  
INV. NO. 2868-W