

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

15-153-20067-00-00

FEB 2 1970

CONSERVATION DIVISION  
Wichita, Kansas

2-2-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Peterson Well No. 2

Location App. CS/2-S/2-SW/4 Sec. 6 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4130'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.         

Operation Completed: Hour 3:45 PM Day 27 Month 1 Year 1970

The above well was plugged as follows:

279'--8 5/8" Surface casing cement circulated with 200 Sx.  
Top of Dakota section @ 1650'.

Circulated hole with heavy mud, pulled DP to 1875' and displaced 100 Sx. cement thru  
DP from 1875' to 1550'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichol*  
Well Plugging Supervisor

INVOICED  
DATE 2/2/70  
INV. NO. 1349-W