

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1974

CONSERVATION DIVISION
Wichita, Kansas

3-6-1974

15-153-19001-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Kasten Well No. 2-A

Location CNW/4 Sec. 2 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4076'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kans. License No. _____

Operation Completed: Hour 7:15 AM Day 2 Month 3 Year 1974

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1950'.

Circulated hole with heavy mud. Pulled DP to 2175' and displaced 110 Cu. Ft. cement
thru DP from 2175' to 1850'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

3/6/74

INV. NO. 8706-u

Signed: M. L. Nichols
Well Plugging Supervisor