

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20176-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
2-27-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Kasten Well No. 2

Location CNW/4 Sec. 2 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 3000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated LOST HOLE due to 1 joint surface casing coming loose
& going down hole, unable to get drill stem below 254'.

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 11:00 PM Day 21 Month 2 Year 1974

The above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1950'.

Squeezed well thru surface casing initially with 3 sacks and followed with 110 Cu. Ft.
cement from 2175' to 1850' then 10 1/2 Bbl. drilling mud from 1850' to 250' and followed
with 30 Cu. Ft. cement from 250' to 175' then 10 Bbl drilling mud from 175' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in press-
ure-300#. Final shut-in pressure-150#. (Mud and cement pumped by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

2/27/74
INV. NO. 8659-02