

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1974
10-29-74
CONSERVATION DIVISION
Wichita, Kansas

15-153-20186-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Stolte Well No. 1

Location NW-NW-SE Sec. 2 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4085'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 24 Month 10 Year 1974

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 110 Cu. Ft. cement
thru DP from 2025' to 1700'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. J. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/31/74
INV. NO. 216-W