

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20168-00-00

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1973  
9-20-73

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Arendt Well No. 1

Location SE-SE-NW Sec. 3 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4150'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 11:00 PM Day 17 Month 9 Year 1973

The above well was plugged as follows:

245'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1975'.

Circulated hole with heavy mud. Pulled DP to 2175' and displaced 110 Cu. Ft. cement  
thru DP from 2175' to 1850'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 9-20-73

Signed: M. L. Nichols  
Well Plugging Supervisor

INV. NO. 7940-02