

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30014-00-00

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1964
2-5-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address: Box #649, McCook, Nebraska.

Lease Name Meyer Well No. A-2

Location Cnw-SE Sec. 19 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4260

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stoeppel werth Drilling, Inc.,

Address: P.O. Drawer#193, Russell, Kans. License No. _____

Operation Completed: Hour 5:15AM Day 1 Month 2 Year 1964

The Above well was plugged as follows:

371'--8 5/8" Surface pipe, cement circulated with 300 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 360', set plug with 1/4 Sk. hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 Sk. hulls

and 10 Sx. cement to bottom of cellar.

(Cementing Operations performed by Halliburton Oil Well Cementing Co.)

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2/6/64
INV. NO. 8596-W

Signed: [Signature]
Well Plugging Supervisor