

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20119-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas
6-21-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Wicke Well No. D-1

Location CNE-NE Sec. 19 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4145'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kans. License No.

Operation Completed: Hour 2:00 PM Day 16 Month 6 Year 1971

The above well was plugged as follows:

320'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 100 Sx. cement thru
DP from 2025' to 1700'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/22/71

INV. NO. 3881-W