

State of Kansas



15-153-30014-00-00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 5 1964  
2-5-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Eddie Braun of Skelly Oil Company has this date requested permission to plug the following described well:

Mr. Braun guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: Box #649, McCook, Nebraska.

Lease Name: Meyer Well No. A-2

Location: CNW-SE Sec. 19 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4260 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Braun was instructed to plug the well as follows:

371'--8 5/8" Surface pipe, cement circulated with 300 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" 360' with 1/4 Sk. hulls & 20 Sx. cement.

" 40' with 1/8 Sk. hulls & 10 Sx. cement.

Very truly yours,

*W. L. Nichols*