

State of Kansas



15-153-30012-00-00

FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1964  
10-13-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this  
date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Munstermann Well No. 2

Location: CNW-SW Sec. 19 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4240 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

267'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	260' with 1/4 sk hulls & 20 Sx. cement.
"	"	40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent