

15-153-20026-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rawlins County, Sec. 6 Twp. 1s Rge. (E) 33 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Empire Drilling Company  
Lease Name Peterson Well No. 1  
Office Address 650 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 8-17 19 68  
Application for plugging filed 4-10 19 70  
Application for plugging approved 4-13 19 70  
Plugging commenced 11-13 19 70  
Plugging completed 11-13 19 70  
Reason for abandonment of well or producing formation Lack of oil  
If a producing well is abandoned, date of last production 3-1 1970  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4120 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface, Sand, Clay, Shale		0	900	8 5/8"	202.36	-0-
				5 1/2"	4150'	1877.63

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

200 sax cement plug 3000'  
5 sax cement plug at 2250' Pulled 1902' 5 1/2' pipe  
Halliburton pumped 5 sax hulls, 12 sax jell, 100 sax cement, 18 sax jell, 25 sax cement, 5 jell and 10 sax cement on top. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-20-70


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor David Litan Cable Tools #654 Docket #89,447-C(C-15,597)  
Address Box 1437 Wichita, Kansas 67201

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Dan J. Kornfeld (partner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld  
650 4th Natl. Bank Bldg., Wichita, Ks. 67202  
(Address)

Subscribed and sworn to before me this 19th day of November, 1970  
September 14, 1972



Kay P. LaGree  
Notary Public.

15-153-20026-00-00

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1970

CONSERVATION DIVISION  
Wichita, Kansas

4-13-70

DRILLER'S LOG

COMPANY	Empire Drilling Company
CONTRACTOR	Leben Drilling, Inc.
FARM	Peterson #1
LOCATION	SE SE SW Section 6-1S-33W Rawlins County, Kansas
COMMENCED	8-9-68
COMPLETED	8-18-68

---

0	40	Clay Rock
40	125	Sand, Clay
125	900	Shale
900	1400	Sand, Shale
1400	1780	Shale, Shells
1780	2160	Shale, Sand. Shale
2160	2525	Shale, Sand
2525	2778	Shale, Anhydrite, Red Bed
2778	2816	Anhydrite
2816	3070	Shale, Red Bed
3070	3235	Shale, Lime
3235	3760	Lime Shale
3760	4118	Lime
	4118	RTD Set @ 5½"

---

Ran 11 Jts. 8 5/8" 8rd 24# Used casing 202.36 @ 210' with 165 sacks  
Common 2% c.c.