



15-153-20040-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 1-20-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Kurfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company & J. S. Kantor,

Complete Address: 617 Union Center Building, Wichita, Kansas,

Lease Name: Horinek Well No. 1-A

Location: App.-NE-NE Sec. 4 Twp. 1 Rge. (E)(W) 33

County: Fawkins Total Depth 4175' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1675'.

Circulate hole with heavy mud. Pull DP to 1900' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. P. [Signature]
 Conservation Division Agent