



15-153-20156-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
5-22-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this  
date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Vap Well No. B-1

Location: Appr: -SE-SE-SE Sec. 4 Twp. 1 Rge. (E) (W) 33

County: Rawlins Total Depth 4110' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

227'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1800'.

Circulate hole with heavy mud. Pull DP to 2025' and displace 110 Cu Ft.  
cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

M. G. Nichols  
Conservation Division Agent