



15-153-20026-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1970
CONSERVATION DIVISION
Wichita, Kansas
11-17-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob White of Empire Drilling Company, has this date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Peterson Well No. 1

Location: SE-SE-SW Sec. 6 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4120' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. White was instructed to plug the well as follows:

- 210'--8 5/8" Surface casing, cement circulated with 165 Sx.
- 4117'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3002'. Bridge plug set @ 2200' and 5 Sx. cement with dump bailer.
- Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx. cement staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent