



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAR 6 1974 3-6-1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kans.

Lease Name: Kasten Well No. 2-A

Location: CNW/4 Sec. 2 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4076' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx. Top of Dakota section @ 1950.'

Circulate hole with heavy mud. Pull DP to 2175' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols Conservation Division Agent