

State of Kansas



15-153-20186-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1974

CONSERVATION DIVISION
Wichita, Kansas

10-29-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kans.

Lease Name: Stolte Well No. 1

Location: NW-NW-SE Sec. 2 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4085' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

248'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2025' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent