



15-153-20038-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 8 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 1-8-1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company and J. S. Kantor,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Horinek Well No. 1

Location: App.-CNE-NE Sec. 4 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 2700 Oil Well     

Gas Well      Input Well      SWD Well      D & A      Lost Hole X

Mr. Favinger was instructed to plug the well as follows:

259'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1675'. Lost circulation @ 2595'. Dry drilled to 2700'. Unable to regain circulation, abandoned hole. Shot off DP @ 1981'.

Well had sanding off on bottom was able to circulate hole from 1900'. Displace 100 Sx. cement thru DP @ 1900'. Pull DP to 270' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
 Conservation Division Agent