

RECEIVED
APR 23 2004
KCC WICHITA

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 272-2963 Operator License #: 4058

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Hubert Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 2952' Bottom: 3194' T.D. 3355'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
NA		surface	900'	85/8	900'	None <u>o</u>
						<u>Prod csg NA</u>
<u>Prod</u>			<u>3359</u>	<u>4.5</u>	<u>3359</u>	<u>o</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1500 to 1501, 950 to 951, 475 to 476, 2spf. Ran 23/8 tbg to 2620'. Swift pumped 70sx 60/40 pos, 10% gel with 400# hulls and displaced to balance. pulled tbg to 1300'. swift pumped 70sx with 300# hulls, Cir to surface. pulled tbg out. Hooked up to 41/2 casing pumped 14sx pressured up 300# blew hole in 41/2. cir thru braden head. Shut casing in. Hooked up to braden head and pumped 160sx. Toped 41/2 off. Cut 85/8 and 41/2 off 6' below surface, Caped and back filled.

Name of Plugging Contractor: Swift Services Inc. Martin Drilling Co, Inc License #: 32382 30606

Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jody Smith

(Address) P.O. Box 399 Garden City Ks. 67846

DEBRA J. PURCELL
Notary Public - State of Kansas
My Appt. Expires 11/4/07

SUBSCRIBED and SWORN TO before me this 22 day of April, 20 04

Debra Purcell My Commission Expires: 11/4/07
Notary Public