

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Shelby Resources LLC  
Address: 5893 Saddle Creek Trail, Parker, Colorado 80134  
Phone: (303) 840-2183 Operator License #: 31725  
Type of Well: oil Docket #: n/a  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4/8/04 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Arbuckle Depth to Top: 3419' Bottom: 3430' T.D. 3422  
LKC Depth to Top: 3230' Bottom: 3232' T.D. 3430  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3462

API Number: 15-163-21153-00-00  
Lease Name: Lowry B  
Well Number: #2  
Spot Location (QQQQ): SW - ne - SW -  
1650 Feet from  North /  South Section Line  
3630 Feet from  East /  West Section Line  
Sec. 20 Twp. 8 S. R. 19  East  West  
County: Rooks  
Date Well Completed: 11/1980  
Plugging Commenced: 4/8/04  
Plugging Completed: 4/8/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC (3176'-3390')	oil, water	surface	290' 305	8 5/8"	290' 305	none
Arbuckle (3419'-30')	oil, water	Prod surface	3419' 3420	4 1/2"	3419' 3420	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 2 3/8" tbg to 2000'. Pump 120 sxs of 60/40 poz, 10% gel w/ 200 # of hulls and cement circulated. Pull tubing and pumped 80 sxs 60/40 poz, 10% gel and 300 # hulls down casing. Pressured up to 900 psi. Shut in at 300 psi. Tied to annulus and pressured up to 700 psi and shut in.

Name of Plugging Contractor: Gaschier Well Service Company Tools License #: 3313799998  
Address: PO Box 141, Ellis, Kansas 67637  
Name of Party Responsible for Plugging Fees: Shelby Resources LLC  
State of Colorado County, DOUGLAS, ss.

RECEIVED  
APR 29 2004  
KCC WICHITA

JAMES A WAECHTER (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) J A Waechter  
(Address) 5893 SADDLE CREEK TR PARKER, CO. 80134

SUBSCRIBED and SWORN TO before me this 26<sup>th</sup> day of APRIL, 2004  
Notary Public  
DOUGLAS G. LILLER  
STATE OF COLORADO  
My Commission Expires 06/29/2005

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Am*