

API NUMBER 15-167-45581-00-01

LEASE NAME Hummel

WELL NUMBER 2

990' Ft. from S Section Line

4290' Ft. from E Section Line

SEC. 30 TWP. 14S RGE. 14 (E) or (W)

COUNTY Russell

Date Well Completed 3-8-63

Plugging Commenced 8-12-03

Plugging Completed 8-12-03

APR 06 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well injection

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-20-03 (date)

by Herb Deines (KCC District Agent's Name).

Is AC-1 filed? yes If not, is well log attached?

Producing Formation Arb Depth to Top _____ Bottom _____ T.O. 3202

Show depth and thickness of all water, oil and gas formations. 3207

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>4203</u>	<u>8 1/2 x 5</u>	<u>4203</u>	<u>A</u>
<u>Prod</u>			<u>3201</u>	<u>5 x 5</u>	<u>3201</u>	<u>B</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Run tbg + catcher to 2840'. Release lockset + pull. Run open ended tbg. to 2956'
Rig up Allied. Pump 100 sx 60/40 pos 10 20 gel 300 # hulls. Pull to 1049'. Pump
170 sx 60/40 pos 10 20 gel 300 # hulls circ to surf on 5 1/2 x 8 5/8. Pull tbg. Put
20 sx down 5 1/2 fill to surf on 5 1/2 x 8 5/8. Witnessed by Jay Pfeifer KCC Hays

Name of Plugging Contractor Berexco, Inc. Company Tools License No. 5363 99998

Address P.O. Box 723 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Bob Grant (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Robert Grant

(Address) P.O. Box 723, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 14th day of August, 2003

Marion Sue Vance
Notary Public

My Commission Expires:

