

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-05297-06-00

API NUMBER 15-4/8/60
LEASE NAME Texaco Cahoj

WELL NUMBER #46
NOTICE: Fill out completely and return to Cons. Div. office within 30 days
2310 Ft. from S Section Line
3630 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 17 TWP1S RGE. 34W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Rawlins
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/8/60
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 3/31/04
Plugging Completed 3/31/04

The plugging proposal was approved on 3/31/04 (date)
by Darrel Dipman w/KCC in Hays, KS (KCC District Agent's Name).
Is ACO-1 filed? No If not, is well log attached? Yes
Producing Formation LKC Depth to Top 4102 Bottom 4188 TD4226 Show depth and thickness of all water oil and gas formations. 4410

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	367	8 5/8	367	0
	Production	Surface	4414	5 1/2	4414	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well as follows:

Ran tbg to 2628'. RU Swift. Pumped 130 sxs SMD cmt w/500# hulls. Pulled tbg to 1189'. Pumped 75 sxs SMD w/250# hulls & circ cmt to surface. TOH w/tbg. Hooked up to 8 5/8". Pumped 25 sxs SMD & 50# hulls. Max press 300#. SI @ 200# & held. Hooked up to 5 1/2" csg. Pumped 25 sxs SMD. Max press 400#. Held 200# for 30 mins. SI. Job completed @ 12:30pm. Witnessed & approved by Darrel Dipman w/KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED
APR 29 2004

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

KCC WICHITA

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28th day of April, 2004

Notary Public - Kristin Grady

Kristin Grady
My Commission Expires: 2/06/08 Form CP-4

Revised 05-88



SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

COPY

DATE	INVOICE #
3/31/04	6393

BILL TO
Murfin Drilling Co Inc PO Box 661 Colby, KS 67701-0661

TEXACO Cahoj #46

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	46	Cahoj	Rawlins		Oil	Abandoned	Lenny	PTA

PRICE REFERE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	120	2.50	300.00T
576W-P	Pump Charge	1	550.00	550.00T
275	Cotton Seed Hulls	11	20.00	220.00T
330	Swift Multi-Density	255	9.75	2,486.25T
581W	Service Charge Cement	275	1.00	275.00T
583W	Drayage	1,362.5	0.85	1,158.13T
	Subtotal			4,989.38
	Out-of-state sale, exempt from sales tax		0.00%	0.00

USED FOR PIA 34
 APPROVED ST

RECEIVED
 APR 29 2004
 KCC WICHITA

Thank you for your business.	Total	\$4,989.38
------------------------------	-------	------------



CHARGE TO: *Muglin Drly Co.*
 ADDRESS:
 CITY, STATE, ZIP CODE: *Colby, Ks*

RECEIVED
 APR 29 2004
 KCC WICHITA

TICKET No 6393

PAGE 1 OF 1

SERVICE LOCATIONS: *Haystack*
 WELL/PROJECT NO.: *46* LEASE: *Cahoj* COUNTY/PARISH: *Rawlins* STATE: *Ks* CITY: DATE: *3-31-04* OWNER: *Same*
 TICKET TYPE: SERVICE SALES CONTRACTOR: RIG NAME/NO.: *Muglin* SHIPPED VIA: *105* DELIVERED TO: *N. W. Atwood* ORDER NO.:
 WELL TYPE: *oil* WELL CATEGORY: *Abandoned* JOB PURPOSE: *P.T.A.* WELL PERMIT NO.: WELL LOCATION:
 REFERRAL LOCATION: INVOICE INSTRUCTIONS:

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575					MILEAGE	120		mi		2.50	300.00
576					Pump charge	1		EA			550.00
275					Hulls	11		SKS		20.00	220.00
330					5mD Cement	255		SKS		9.75	2486.25
581					Bulk service charge	275					275.00
583					Drayage	100	1362	50	T.M.	85	1158.13

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

TO BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO DEPARTURE OF WORK OR DELIVERY OF GOODS

SIGNED: *[Signature]* TIME SIGNED: *9:00* A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4989.38
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				4989.38

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

OPERATOR: *[Signature]* APPROVAL:

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE **3-31-04** PAGE NO. **7**

CUSTOMER **Mingini Dalg Co.**

WELL NO. **46**

LEASE **Cahoj**

JOB TYPE **P.T.A.**

TICKET NO. **6393**

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0845							on LOC T.D. CIBP 4243 Perfs 4185-88, 4102-06
30 cmt 500 hulls	0925	4.5	73800			550		open end Tbg at 2628 Pump 130SKS smp w/ 500 #hulls circ to pit w/oil w/25BBC out Pull Tbg to 1200'
5 cmt 50 Hulls	0945		43880					Hook up at 1200' Pump 75SKS smp w/ 250 #hulls + circ cmt to Scuf Pull Tbg out of hole
	1030		13					Hook up to 8 5/8 + Pump 25SKS cmt + 50 lbs Hulls 300 max PSI shut in 200PSI
	1130		12			400/200		Hook up to 5 1/2 Pump 25SKS cmt max PSI 400 shut in 200PSI
	1230					400/200		Job Complete

RECEIVED
APR 29 2004
KGC WICHITA