

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

15-007-01261-00-00

Lease Operator: Herman L. Loeb

Address: P.O. Box 524, Lawrenceville, IL 62439

Phone: (812) 853-3813 Operator License #: 3273

Type of Well: Oilwell Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4-16-04 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 4468' Bottom: 4496' T.D. 4536'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4570  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - NA drilled 10/55

Lease Name: Newkirk

Well Number: #9

Spot Location (QQQQ): NW - NE - NW -

330 Feet from  North /  South Section Line

1650' Feet from  East /  West Section Line

Sec. 20 Twp. 33 S. R. 11  East  West

County: Barber

Date Well Completed: NA

Plugging Commenced: 4-16-04

Plugging Completed: 4-20-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surf</u>				<u>8 5/8</u>	<u>262'</u>	<u>0</u>
<u>Prod</u>				<u>5 1/2</u>	<u>4570'</u>	<u>2100'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Clarke Corp. Rods and tbq. are stuck. Back rods and tbq. off @ 2141' Run pkr. to 2086' and pump 100 sxs class A cement around fish. Bottom of cement plug @ 3650', top @ 2535'. Pressure test to 1200#. Lay down tbq. Cut 5 1/2 @ 2100'. Pull 5 1/2 to 2055' and spot 50 sxs cement. Lay down 5 1/2. Run 2 3/8 to 600' and pump 10 sxs gel, and 50 sxs cement. Pull tbq. to 290' and pump 50 sxs cement, pull tbq. to 60' and circ. cement to surface. 60/40 6%gel. RDMO


Name of Plugging Contractor: Clarke Corp. License #: 5105

Address: 107 W. Fowler, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Herman L. Loeb

State of Kansas County, Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Alan Vratil

(Address) 509 N. Cedar, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 21 day of April, 2004

Glenda Morrison My Commission Expires: 11/30/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
APR 27 2004  
KCC WICHITA

*Bm*