

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-007-22818-0000
LEASE NAME Prothe
WELL NUMBER 1-12

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2510 Ft. from North Line of Section
950 Ft. from West Line of Section

LEASE OPERATOR Anderson Energy, Inc. SPOT LOCATION S/2 SE SW NW
ADDRESS 221 S. Broadway Section 12 Townshp 33s Range 12w
CITY, STATE, ZIP Wichita, Kansas 67206 County Barber
PHONE # 316-263-1006 Date Well Completed April 21, 2004
Character of Well Dry and Abandoned Date Plugging Commenced April 21, 2004
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed April 21, 2004

The plugging proposal was approved on 04/21/04 (date)
by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3403

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	180	310	8-5/8"	299	0'
Red Surf			299	8.625	299	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Received plugging orders from Steve Pfeifer on 04/21/04. Plugging began 10:15 am on 04/21/04.

Heavy mud in hole and between all plugs. Plugged with total of 135sx 60/40 Poz, 6% Gel.

Bottom plug @ 600' with 50 sx, 2nd plug @ 330' with 50 sx, top plug @ 40' with 10 sx and

plugged rathole with 15 sx, mousehole 10 sx. Plug down at 12:00 pm on 04/21/04.

Acid Services ticket #8509. SDC reported plugging to KCC (Steve Pfeifer) on 04/21/04.

RECEIVED

APR 26 2004

KCC WICHITA

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anderson Energy, Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 23rd day of April, 2004



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Prothe 1-12

LOCATION: S/2 SE SW NW
API: 15-007-22818-0000

Section 12 T 33s R 12w
Barber County, Kansas

OWNER: Anderson Energy, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 14-Apr-04
COMPLETED: 21-Apr-04

TOTAL DEPTH: **DRILLER** 3403 FEET
LOGGER Not Logged FEET

Ground Elevation: 1416
KB Elevation: 1425

LOG

0 -	3 FEET	Top Soil
3 -	180 FEET	Surface Sands and Clay
180 -	1750 FEET	Redbeds, Shales and Salt
1750 -	3403 FEET	Limestone, Shale and Dolomite

CASING RECORDS

Surface Casing-8-5/8"

Spud @ 5:15 pm on 04/14/04. Drilled 12-1/4" hole to 315'. Ran 7 joints of new 23# 8-5/8" surface casing, tally 298.68' set at 309.68' KB. Strapped bottom 3 joints, welded collars on other 4 joints. Cemented with 220 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# celloflake per sx. Cement did circulate. Plug down @ 11:30 pm on 04/14/04. By Acid Services, ticket # 8283.

Plugging Data:

Received plugging orders from Steve Pfeifer on 04/21/04. Plugging began 10:15 am on 04/21/04. Heavy mud in hole and between all plugs. Plugged with total of 135sx 60/40 Poz, 6% Gel. Bottom plug @ 600' with 50 sx, 2nd plug @ 330' with 50 sx, top plug @ 40' with 10 sx and plugged rathole with 15 sx, mousehole 10 sx. Plug down at 12:00 pm on 04/21/04. Acid Services ticket #8509. SDC reported plugging to KCC (Steve Pfeifer) on 04/21/04.

DEVIATION SURVEYS

1/4 degree(s) at	315	feet
1/4 degree(s) at	1423	feet
1/4 degree(s) at	2294	feet
1-1/4 degree(s) at	3225	feet
1 degree(s) at	3398	feet

RECEIVED
APR 26 2004
KCC WICHITA