

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION FEB 18 2004 OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Webco Oil Company, Inc. Address: 2136 NE 90th Ave., Hoisington, Ks 67544 Phone: (620) 587-3539 Operator License #: 6357 Type of Well: Oil Docket #: The plugging proposal was approved on: February 9th, 2004 by: Pat Staab (KCC District Agent's Name) Is ACO-1 filed? [] Yes [x] No If not, is well log attached? [] Yes [x] No Producing Formation(s): List All (If needed attach another sheet) Anhydrite Depth: 747' Depth to Top: 2973' Bottom: 3300' T.D. 3321'

API Number: 15-009-22,509-00-00 Lease Name: Prosser Well Number: #2 Spot Location (QQQQ): 100'S - SE - NE - SE 1650 Feet from [] North / [x] South Section Line 330 Feet from [x] East / [] West Section Line Sec. 33 Twp. 16 S. R. 12 [] East [x] West County: Barton Date Well Completed: 5/20/2004 3 Plugging Commenced: 02/16/04 Plugging Completed: 02/11/04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface (0' to 360', 8-5/8" casing), Production (0' to 3319', 5-1/2" casing), and two rows for C.I.B.P. (0' to 3300' and 0' to 3317').

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Drove to location. Had pit and well head dug out. Run bailer to check bottom - got all the way down. Sand off 400'. Brackeen Line got 40 barrels total in hole. Rigged up jacks. Pulled slips and casing head. Worked casing. Spot 5 sks cement. Worked casing a bit more. Run in hole with knife and cut casing @ approx. 1550'. Pull to 1425' - spot 100 sks & 300# hulls & 2 bbls flush. Pull to 775' - spot 50 sks & 100# hulls. Pull to 300' - spot 65 sks & 100# hulls. Pull rest of casing - top with 10 sks. Rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc License #: 6901 Address: P.O. Box 231, Claflin, Kansas 67525 Name of Party Responsible for Plugging Fees: Webco Oil Company, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL Notary Public - State of Kansas My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich (Address) P.O. Box 231, Claflin, Ks 67525

SUBSCRIBED and SWORN TO before me this 13th day of February, 2004 My Commission Expires: 4/13/06