

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-153-20939-00-01

API NUMBER 15-153-20,539-A

LEASE NAME RATHER

WELL NUMBER 1

SPOT LOCATION SW SW NW

SEC. 3 TWP. 1S RGE. 33 ~~XXXX~~ (W)

COUNTY Rawlins

Date Well Completed 07/26/86

Plugging Commenced 07/26/86

Plugging Completed 07/26/86

LEASE OPERATOR TEXAS PETROLEUM RESOURCES

ADDRESS P.O. Box 2508, Amarillo, Tx. 79105

PHONE # (806) 371-7566 OPERATORS LICENSE NO. 9665

Character of Well D & A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas
 (By Previous Operator)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation N?A Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	308'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

25 sx. 60/40 PozMix + 6% Gel from 2,816'-2,742' Plug #1
 100 sx. 60/40 PozMix + 6% Gel from 2,126'-1,830' Plug #2
 40 sx. 60/40 PozMix + 6% Gel from 330'-Surface Plug #3
 10 sx. 60/40 PozMix + 6% Gel from 0'-30' Plug #4
 10 sx. 60/40 PozMix + 6% Gel - Mousehole and 15 sx. 60/40 PozMix + 6% Gel - Rathole
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Golden Eagle Drilling License No. 8682
 Address P. O. Box 983, McCook, Ne. 69001

STATE OF TEXAS COUNTY OF VICTORIA, ss. 8-22-86

James L. Lewis (employee of operator) or
~~XXXXXX~~ of above-described well, being first duly sworn on oath, says, AUG 22 1986
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God.

(Signature) James L. Lewis
 (Address) P. O. Box 3723, Victoria, Tx.

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1986

Barbara Orsak
 Notary Public
 Barbara Orsak

My Commission expires: 06/11/90

Reference to API Number, this was an attempted re-entry, OWWO.
 Total depth was not reached and well was plugged without logs.
 Previous Operator, Berexco, Inc. Re-entry stopped at 3,000'.
 Form CP-4 /-84
 Revised 06-83