

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20172-00-00

11-6-73  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Prochazka Well No. 1

Location GSW-SW Sec. 7 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4230'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 8:00 PM Day 2 Month 11 Year 1973

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1825'.

Circulated hole with heavy mud. Pulled DP to 2050' and displaced 110 Cu. Ft. cement  
thru DP from 2050' to 1725'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

~~INVOICED~~

I hereby certify that the above well was plugged as herein stated.

DATE 11/7/73

INV. NO. 8129-W

Signed: H. L. Nichols  
Well Plugging Supervisor