

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1961

CONSERVATION DIVISION  
Wichita, Kansas

7-11-61

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-153-30043-00-00

File No. \_\_\_\_\_ County: Rawlins

Location: CNW NE Sec. 8 Twp. \_\_\_\_\_ Rge. 1 (E) \_\_\_\_\_ (W) 33

Name of Field: \_\_\_\_\_ Total Depth: 4680

I have this date completed supervision of plugging of:

Lease Name: Peterson Well No. 1

Operator's Full Name: Leben Drg Co

Complete Address: 905 Central Bldg Wichita, Kansas

Plugging Contractor same

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A x

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No x

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5AM Day 6 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 237' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 600', displaced 20  
sax cement through drill pipe, heavy mud to 180', set plug and 20 sax  
cement, heavy mud to 40', set plug, 1/2 sack hulls and 10 sax cement  
to bottom cellar.

Signed: Edson Peety  
Conservation Division Agent

Reviewed: David Morris  
Field Supervisor

Remarks:

INVOICED  
DATE 7/20/61  
INV. NO. 3448-W