

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20765-00-00
Spot: SE^{NE}ENW Sec/Twnshp/Rge: 15-22S-4E
990 feet from N Section Line, 2250 feet from W Section Line
Lease Name: BURTON M E Well #: 4
County: MARION Total Vertical Depth: 2532 feet

Operator License No.: 6131
Op Name: DRILLER'S AND PRODUCER'S, INC.
Address: PO BOX 385
NEWTON, KS 67114

PROD Size: 5.5 feet: 2529 50 SX CMT
SURF Size: 8.625 feet: 181 125 SX CMT

\$ 82,29

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2004 9:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: BILLY ROGERS Company: DRILLER'S & PRODUCER'S, INC. Phone: (620) 382-7212

Proposed Plugging Method: Sand to 2,480' and spot 5 sxs. cement. Shoot pipe off. Pull pipe to 250' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/01/2004 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Ran tubing to 2,520' and spotted 10 sxs. cement Shot pipe off at 1,140' and pulled same. Ran 2 3/8" tubing to 252' and circulated 118 sxs. cement to the surface.

RECEIVED
KCC DISTRICT #2
APR 16 2004
WICHITA, KS

Remarks: USED COMMON CEMENT BY C & G DRILLING, INC. INVOICE #003.

Plugged through: TBG

District: 02

Signed Michael P R Wilson
(TECHNICIAN)

INVOICED
DATE 4-20-04
INV. NO. 2004061440